

New Mixed Use Building
82 NW 5th Ave. – West Settlers Building

SECTION 018113.13 - SUSTAINABLE DESIGN REQUIREMENTS - LEED FOR NEW CONSTRUCTION AND MAJOR RENOVATIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes general requirements and procedures for compliance with certain USGBC LEED prerequisites and credits needed for Project to obtain LEED-Certified Silver certification based on USGBC's "LEED 2009 for New Construction & Major Renovations."

- 1. Other LEED prerequisites and credits needed to obtain LEED certification depend on product selections and may not be specifically identified as LEED requirements. Compliance with requirements needed to obtain LEED prerequisites and credits may be used as one criterion to evaluate substitution requests and comparable product requests.
- 2. Additional LEED prerequisites and credits needed to obtain the indicated LEED certification depend on Architect's design and other aspects of Project that are not part of the Work of the Contract.
- 3. A copy of the LEED Project checklist is attached at the end of this Section for information only.

- B. Related Requirements:

- 1. Divisions 01 through 33 Sections for LEED requirements specific to the work of each of these Sections. Requirements may or may not include reference to LEED.

1.3 DEFINITIONS

- A. Chain-of-Custody Certificates: Certificates signed by manufacturers certifying that wood used to make products was obtained from forests certified by an FSC-accredited certification body to comply with FSC STD-01-001, "FSC Principles and Criteria for Forest Stewardship." Certificates shall include evidence that manufacturer is certified for chain of custody by an FSC-accredited certification body.
- B. Regional Materials: Materials that have been extracted, harvested, or recovered, as well as manufactured, within 500 miles (800 km) of Project site. If only a fraction of a product or material is extracted/harvested/recovered and manufactured locally, then only that percentage (by weight) shall contribute to the regional value.
- C. Recycled Content: The recycled content value of a material assembly shall be determined by weight. The recycled fraction of the assembly is then multiplied by the cost of assembly to determine the recycled content value.
 - 1. "Post-consumer" material is defined as waste material generated by households or by commercial, industrial, and institutional facilities in their role as end users of the product, which can no longer be used for its intended purpose.

New Mixed Use Building
82 NW 5th Ave. – West Settlers Building

2. "Pre-consumer" material is defined as material diverted from the waste stream during the manufacturing process. Excluded is reutilization of materials such as rework, regrind, or scrap generated in a process and capable of being reclaimed within the same process that generated it.

1.4 ADMINISTRATIVE REQUIREMENTS

- A. Respond to questions and requests from Architect and the USGBC regarding LEED credits that are the responsibility of the Contractor, that depend on product selection or product qualities, or that depend on Contractor's procedures until the USGBC has made its determination on the project's LEED certification application. Document responses as informational submittals.

1.5 ACTION SUBMITTALS

- A. General: Submit additional LEED submittals required by other Specification Sections.
- B. LEED submittals are in addition to other submittals. If submitted item is identical to that submitted to comply with other requirements, submit duplicate copies as a separate submittal to verify compliance with indicated LEED requirements.
- C. LEED Documentation Submittals:
 1. Credit EA 5: Product data and wiring diagrams for sensors and data collection system used to provide continuous metering of building energy-consumption performance over a period of time of not less than one year of post construction occupancy.
 2. Credit MR 2: Comply with Division 01 Section "Construction Waste Management and Disposal."
 3. Credit MR 4: Product data and certification letter indicating percentages by weight of post-consumer and pre-consumer recycled content for products having recycled content. Include statement indicating cost for each product having recycled content.
 4. Credit MR 5: Product data for regional materials indicating location and distance from Project of material manufacturer and point of extraction, harvest, or recovery for each raw material. Include statement indicating cost for each regional material and the fraction by weight that is considered regional.
 5. Credit MR 7: Product data and chain-of-custody certificates for products containing certified wood. Include statement indicating cost for each certified wood product.
 6. Credit IEQ 3.1:
 - a. Construction indoor-air-quality management plan.
 - b. Product data for temporary filtration media.
 - c. Product data for filtration media used during occupancy.
 - d. Construction Documentation: Six photographs at three different times during the construction period, along with a brief description of the SMACNA approach employed, documenting implementation of the indoor-air-quality management measures, such as protection of ducts and on-site stored or installed absorptive materials.
 7. Credit IEQ 4.1: Product data for adhesives and sealants used inside the weatherproofing system indicating VOC content of each product used.
 8. Credit IEQ 4.2: Product data for paints and coatings used inside the weatherproofing system indicating VOC content of each product used.
 9. Credit IEQ 4.4: Product data for products containing composite wood or agrifiber products or wood glues indicating that they do not contain urea-formaldehyde resin.

1.6 INFORMATIONAL SUBMITTALS

New Mixed Use Building
82 NW 5th Ave. – West Settlers Building

- A. Qualification Data: For LEED coordinator.
- B. Project Materials Cost Data: Provide statement indicating total cost for materials used for Project. Costs exclude labor, overhead, and profit. Include breakout of costs for the following categories of items:
 - 1. Furniture.
 - 2. Plumbing.
 - 3. Mechanical.
 - 4. Electrical.
 - 5. Specialty items such as elevators and equipment.
 - 6. Wood-based construction materials.
- C. LEED Action Plans: Provide preliminary submittals within 30 days of date established for commencement of the Work indicating how the following requirements will be met:
 - 1. Credit MR 2: Waste management plan complying with Division 01 Section "Construction Waste Management and Disposal."
 - 2. Credit MR 4: List of proposed materials with recycled content. Indicate cost, post-consumer recycled content, and pre-consumer recycled content for each product having recycled content.
 - 3. Credit MR 5: List of proposed regional materials. Identify each regional material, including its source, cost, and the fraction by weight that is considered regional.
 - 4. Credit MR 7: List of proposed certified wood products. Indicate each product containing certified wood, including its source and cost of certified wood products.
 - 5. Credit IEQ 3.1: Construction indoor-air-quality management plan.
- D. LEED Progress Reports: Concurrent with each Application for Payment, submit reports comparing actual construction and purchasing activities with LEED action plans for the following:
 - 1. Credit MR 2: Waste reduction progress reports complying with Division 01 Section "Construction Waste Management and Disposal."
 - 2. Credit MR 4: Recycled content.
 - 3. Credit MR 5: Regional materials.
 - 4. Credit MR 7: Certified wood products.

1.7 QUALITY ASSURANCE

- A. LEED Coordinator: Engage an experienced LEED-Accredited Professional to coordinate LEED requirements. LEED coordinator may also serve as waste management coordinator.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. Provide products and procedures necessary to obtain LEED credits required in this Section. Although other Sections may specify some requirements that contribute to LEED credits, the Contractor shall determine additional materials and procedures necessary to obtain LEED credits indicated.

2.2 RECYCLED CONTENT OF MATERIALS

New Mixed Use Building
82 NW 5th Ave. – West Settlers Building

- A. Credit MR 4: Building materials shall have recycled content such that post-consumer recycled content plus one-half of pre-consumer recycled content for Project constitutes a minimum of 10 percent of cost of materials used for Project.
1. Cost of post-consumer recycled content plus one-half of pre-consumer recycled content of an item shall be determined by dividing weight of post-consumer recycled content plus one-half of pre-consumer recycled content in the item by total weight of the item and multiplying by cost of the item.
 2. Do not include furniture, plumbing, mechanical and electrical components, and specialty items such as elevators and equipment in the calculation.

2.3 REGIONAL MATERIALS

- A. Credit MR 5: Not less than 10 percent of building materials (by cost) shall be regional materials.

2.4 CERTIFIED WOOD

- A. Credit MR 7: Not less than 50 percent (by cost) of wood-based materials shall be produced from wood obtained from forests certified by an FSC-accredited certification body to comply with FSC STD-01-001, "FSC Principles and Criteria for Forest Stewardship."
1. Wood-based materials include, but are not limited to, the following materials when made from wood, engineered wood products, or wood-based panel products:
 - a. Rough carpentry.
 - b. Miscellaneous carpentry.
 - c. Heavy timber construction.
 - d. Wood decking.
 - e. Metal-plate-connected wood trusses.
 - f. Structural glued-laminated timber.
 - g. Finish carpentry.
 - h. Architectural woodwork.
 - i. Wood paneling.
 - j. Wood veneer wall covering.
 - k. Wood flooring.
 - l. Wood lockers.
 - m. Wood cabinets.
 - n. Furniture.

2.5 LOW-EMITTING MATERIALS

- A. Credit IEQ 4.1: For field applications that are inside the weatherproofing system, adhesives and sealants shall comply with the following VOC content limits when calculated according to 40 CFR 59, Subpart D (EPA Method 24):
1. Wood Glues: 30 g/L.
 2. Metal-to-Metal Adhesives: 30 g/L.
 3. Adhesives for Porous Materials (Except Wood): 50 g/L.
 4. Subfloor Adhesives: 50 g/L.
 5. Plastic Foam Adhesives: 50 g/L.
 6. Carpet Adhesives: 50 g/L.
 7. Carpet Pad Adhesives: 50 g/L.

New Mixed Use Building
82 NW 5th Ave. – West Settlers Building

8. VCT and Asphalt Tile Adhesives: 50 g/L.
 9. Cove Base Adhesives: 50 g/L.
 10. Gypsum Board and Panel Adhesives: 50 g/L.
 11. Rubber Floor Adhesives: 60 g/L.
 12. Ceramic Tile Adhesives: 65 g/L.
 13. Multipurpose Construction Adhesives: 70 g/L.
 14. Fiberglass Adhesives: 80 g/L.
 15. Contact Adhesive: 80 g/L.
 16. Structural Glazing Adhesives: 100 g/L.
 17. Wood Flooring Adhesive: 100 g/L.
 18. Structural Wood Member Adhesive: 140 g/L.
 19. Single-Ply Roof Membrane Adhesive: 250 g/L.
 20. Special-Purpose Contact Adhesive (contact adhesive that is used to bond melamine-covered board, metal, unsupported vinyl, rubber, or wood veneer 1/16 inch or less in thickness to any surface): 250 g/L.
 21. Top and Trim Adhesive: 250 g/L.
 22. Plastic Cement Welding Compounds: 250 g/L.
 23. ABS Welding Compounds: 325 g/L.
 24. CPVC Welding Compounds: 490 g/L.
 25. PVC Welding Compounds: 510 g/L.
 26. Adhesive Primer for Plastic: 550 g/L.
 27. Sheet-Applied Rubber Lining Adhesive: 850 g/L.
 28. Aerosol Adhesive, General-Purpose Mist Spray: 65 percent by weight.
 29. Aerosol Adhesive, General-Purpose Web Spray: 55 percent by weight.
 30. Special-Purpose Aerosol Adhesive (All Types): 70 percent by weight.
 31. Other Adhesives: 250 g/L.
 32. Architectural Sealants: 250 g/L.
 33. Nonmembrane Roof Sealants: 300 g/L.
 34. Single-Ply Roof Membrane Sealants: 450 g/L.
 35. Other Sealants: 420 g/L.
 36. Sealant Primers for Nonporous Substrates: 250 g/L.
 37. Sealant Primers for Porous Substrates: 775 g/L.
 38. Modified Bituminous Sealant Primers: 500 g/L.
 39. Other Sealant Primers: 750 g/L.
- B. Credit IEQ 4.2: For field applications that are inside the weatherproofing system, paints and coatings shall comply with the following VOC content limits when calculated according to 40 CFR 59, Subpart D (EPA Method 24):
1. Flat Paints and Coatings: VOC not more than 50 g/L.
 2. Nonflat Paints and Coatings: VOC not more than 150 g/L.
 3. Dry-Fog Coatings: VOC not more than 400 g/L.
 4. Primers, Sealers, and Undercoaters: VOC not more than 200 g/L.
 5. Anticorrosive and Antirust Paints Applied to Ferrous Metals: VOC not more than 250 g/L.
 6. Zinc-Rich Industrial Maintenance Primers: VOC not more than 340 g/L.
 7. Pretreatment Wash Primers: VOC not more than 420 g/L.
 8. Clear Wood Finishes, Varnishes: VOC not more than 350 g/L.
 9. Clear Wood Finishes, Lacquers: VOC not more than 550 g/L.
 10. Floor Coatings: VOC not more than 100 g/L.
 11. Shellacs, Clear: VOC not more than 730 g/L.
 12. Shellacs, Pigmented: VOC not more than 550 g/L.
 13. Stains: VOC not more than 250 g/L.
- C. Credit IEQ 4.4: Composite wood, agrifiber products, and adhesives shall not contain urea-formaldehyde resin.

New Mixed Use Building
82 NW 5th Ave. – West Settlers Building

PART 3 - EXECUTION

3.1 MEASUREMENT AND VERIFICATION

- A. Credit EA 5: Implement measurement and verification plan consistent with Option B: Energy Conservation Measure Isolation in the EVO's "International Performance Measurement and Verification Protocol (IPMVP), Volume III: Concepts and Options for Determining Energy Savings in New Construction," and as further defined by the following:
 - I. To be determined (plan to be implemented).
- B. If not already in place, install metering equipment to measure energy usage. Monitor, record, and trend log measurements.
- C. Evaluate energy performance and efficiency by comparing actual to predicted performance.
- D. Measurement and verification period shall cover at least one year of postconstruction occupancy.

3.2 CONSTRUCTION WASTE MANAGEMENT

- A. Credit MR 2: Comply with Division 01 Section "Construction Waste Management and Disposal."

3.3 CONSTRUCTION INDOOR-AIR-QUALITY MANAGEMENT

- A. Credit IEQ 3.1: Comply with SMACNA's "SMACNA IAQ Guideline for Occupied Buildings under Construction."
 - 1. If Owner authorizes use of permanent heating, cooling, and ventilating systems during construction period as specified in Division 01 Section "Temporary Facilities and Controls," install filter media having a MERV 8 according to ASHRAE 52.2 at each return-air inlet for the air-handling system used during construction.
 - 2. Replace all air filters immediately prior to occupancy.

END OF SECTION 018113.13